

## **APPENDIX 2: CASE STUDY**


**Caltrans Contract No.: 11-413604**

**Location: Interstate 8 in Imperial County near El Centro From 0.6 Mile West of Anderholt Road Overcrossing To 0.5 Mile East of East Highline Canal Bridge.**


**Reference: David Evans, Caltrans District 11 Pavement Engineer**



## Alternate Non-Stabilized Section



## TriAx Geogrid NSSP Enhanced Section



## Caltrans I-8 Update

### PROJECT NAME

Contract No. 11-413604 (Segment 1)  
Interstate 8 in Imperial County near El Centro From 0.6 Mile West of Anderholt Road Overcrossing To 0.5 Mile East of East Highline Canal Bridge

### PRODUCT

TriAx® Geogrid Non-Standard Special Provision (NSSP)

### QUANTITY

200,000 square yards

### OWNER

Caltrans

### CONTRACTOR

Coffman

### INSTALLATION DATE

2016

### PROJECT DETAILS

The project consisted of many challenges:

- Unsuitable Subgrade
- Overbudget
- Time Delays

Caltrans District 11 chose to use Tensor TriAx NSSP geogrid with 0.5' Class 2 Aggregate Subbase (AS), which provided a firm unyielding surface for the Asphalt Paver. The mechanically stabilized geogrid layer (MSL) provided the following savings:


1. Reduced Road Section Thicknesses
2. Reduced environmental impact, material and time savings  
time savings estimated:
  - 60,000CY OF Imported AS material
  - 60,000CY of Export Subgrade
  - 11,000 Trucks
3. Improved Pavement Performance and Longevity





## Location

### Reconstruction of Interstate 8 (SEGMENT LOCATION ONE)







## Caltrans I-8 Update







**SPECTRA®**  
ROADWAY IMPROVEMENT SYSTEM

Caltrans I-8 Update



**Firm and  
unyielding surface  
achieved**

A close-up photograph of a large, heavy-duty yellow roller tire with a deep tread pattern, resting on a coarse gravel surface. The tire is part of a larger yellow machine, likely a road roller, used for compacting aggregate materials.





## RESEARCH

Tensor contracted with Ingios to perform Automated Plate Load Testing on the stabilized section to measure the resilient modulus( $M_r$ ) of the:

- Subgrade (Type III)
- Mechanically Stabilized Layer(MSL), consisting of 0.50 Feet AS Placed on TriAx Geogrid and
- Composite section, MSL and subgrade

The purpose of the testing was to verify the performance of the planned CRCP section along the westbound lanes. Additionally, in situ measurements can assist in a potential redesign of the forthcoming construction of the eastbound lanes. Additionally, the testing provides further validation for Tensor's mechanistic design capabilities.

## RESULTS

- The MSL of 0.50 Feet AS Placed on TriAx Geogrid placed on Type III subgrade, provided both a firm and unyielding surface for construction equipment and the final surface provided support characteristics of a Type I subgrade.
- Estimated Savings on the project by using the TriAx MSL design and not using the alternative of over-excavating an additional 1.0 to 1.5 feet was \$24/SY to \$36/SY.



**Tensor**®

Tensor International Corporation  
2500 Northwinds Parkway  
Suite 500  
Alpharetta, GA 30009  
TensorCorp.com  
800-TENSAR-1