



## PROJECT

Mentor Marsh Interceptor Replacement

## LOCATION

Mentor, OH

## OWNER

Lake County Utilities

## CONTRACTOR

Mark Haynes Construction

## ENGINEER

CT Consultants, Inc.

## INSTALLATION DATE

March-May 2018

## PROJECT DETAILS

Temporary heavy use (max axle load = 25 kips) construction haul road needed for completion of Mentor Marsh Interceptor sewer replacement project. Tensar recommended a design solution of 18" of size 1 and 2 aggregate on top of TX190L Geogrid with a 4 oz. non-woven geotextile underneath to prevent migration of fines from subgrade into the stone layer.

Additionally, TX160 was used in conjunction with TX190L as part of a double layered design over parts of the project area with CBR<1%.

Haul road and geogrid removed after construction and wetland area returned to its original condition.



## PRODUCT

TriAx® TX190L Geogrid  
17,700 square yards

TriAx® TX160 Geogrid  
4,300 square yards

**IN PARTNERSHIP WITH:**

**PS** Construction  
Fabrics, Inc.  
"Contractors in Geotextiles and Pavement Maintenance"

TX\_PP\_OH\_MentorMarsh\_08.18

# CASE STUDY

# Tensor®

